BS 5975:2019 BRITISH STANDARD

Table 1 - Implementation risk classes for temporary works and examples of mitigation measures

Implementation	Risk	Permits required	Other control
risk class			measures
Verylow	No identified practical mode of	N/A	Control via RAMS.
	failure.		Inspection by site
	<ul> <li>No impact if failure occurs.</li> </ul>		team, not necessarily
			recorded on the
			temporary works
			register and might not
		B 1 1 1	require a design brief.
Low	<ul> <li>Minor structures with high levels of robustness.</li> </ul>	Permits can be signed by a TWC or an authorized TWS.	Follow company procedures, including inspection and test plan (see Clause 14).
	levels of robustness.		
	<ul> <li>Very experienced workforce.</li> </ul>		
	Failure is entirely within the		(See Shalle 2.1).
	site, of low impact. Inconvenient,		
	but personal injury unlikely.		
Medium	Conventional structures.	Permits can be signed	Follow company
	Conventional construction	by the PC's TWC or an	procedures, including
	methods.	authorized TWC.	inspection and test plan (see Clause 14).
	Relatively experienced		(see <u>clause 14</u> ).
	workforce.		
	<ul> <li>Failure would be major,</li> </ul>		
	potentially involving injury,		
	fatality or significant economic		
	loss. Would not initiate secondary events.		
High	Schemes with dependency	Permits signed by PC's	Follow company
	on critical structural details.	TWC.	procedures, including
	with little or no redundancy, or		inspection and test plan
	with stability reliant on critical		(see <u>Clause</u> <u>14</u> ).
	elements.		PC's DI to ensure the
	Schemes with complex		scheme is reviewed, e.g.
	interfaces where various items of		HAZOP or peer review.
	temporary works impact on one		
	another		
	Inexperienced workforce.		
	Unfamiliar processes or		
	equipment		
	Failure would be catastrophic		
	in its own right, or if minor might		
	initiate a secondary or chain		
	reaction of major or catastrophic		
	events.		

NOTE 1 The TWC's and TWS's scope of work is covered in  $\underline{11.2.2}$ ,  $\underline{11.3.2}$  and  $\underline{12.2}$  respectively.

 ${\it NOTE 2} \quad {\it The PC's TWC agrees the signatory for each permit applicable to the item of temporary works.}$ 

 ${\it NOTE 3} \quad {\it It is outside the scope of this British Standard to classify particular temporary works.}$